

STANDARD SPECIFICATIONS  
SECTION 01770  
PROJECT CLEANUP

PART 1 GENERAL

1.1 DESCRIPTION

- A. Section includes requirements for cleanup, restabilization, and restoration to prevent accidents to personnel, public, and Commission employees, to protect work in place, restabilize, and restore disturbed areas, removal of evidence of construction activities, and to complete Project in orderly manner.

1.2 CLEANUP

- A. Proceed with construction cleanup as construction progresses.
  - 1. Remove mud, oil, grease, soil, gravel, trash, scrap, debris, and excess materials that are unsightly or may cause accidents to persons or properties.
  - 2. Remove water from floor areas where electrical power tools are to be used, and prevent stains on concrete that will be exposed in finish work.
  - 3. Select and employ cleaning materials and equipment with care to avoid scratching, marring, defacing, staining, or discoloring surfaces cleaned.
- B. Final Cleanup: Perform immediately before written request for final inspection of Project work or any portion thereof.
- C. Besides normal "Broom Clean" requirements, clean exposed surfaces as listed.
  - 1. Glass: Wash and polish.
  - 2. Painted Surfaces: Remove marks, stains, fingerprints, and dirt.
  - 3. Exposed Slabs: Wash, scrape, and scrub, using detergent to remove bond breaker, dirt, and discolorations.
  - 4. Asphalt Paving: Remove mud, oil, grease, dirt, and trash and hose down.
  - 5. Aluminum: Clean following manufacturer's recommendations.
  - 6. Other Surfaces: Remove blemishes, leave clean, uniform, and dust-free.
  - 7. Premises and Site: Remove trash, debris, and surplus excavated material.
- D. Leave premises orderly and "Broom Clean."

1.3 RESTORATION AND RESTABILIZATION

- A. Restore and restabilize disturbed areas including, but not limited to staging and stockpiling areas, construction strips, access roads, stream crossings, and areas within acquired right of way.

- B. Proceed with final restoration and restabilization following Restoration Schedule on Drawings and requirements in Sections 02315 and 02920, including seeding, sodding, and paving when season allows.
- C. Disassemble and remove all temporary construction facilities, and leave site in orderly and restored condition following Contract Documents.
- D. Preserve public and private signs, markers, guardrails, and fences, and maintain in existing locations and condition unless written permission is obtained for removal and restoration or replacement.
  - 1. Remove conflicting facilities when grading operations begin and store in manner to keep them clean and in existing condition.
  - 2. Restore to original or new locations.
  - 3. Repair or replace damaged items when directed.
- E. Perform restoration of turf areas following Section 02920.
- F. Perform tree protection, repair, and replacement following Section 02230.
- G. Restore gravel surfaces and roadway shoulders to their condition before being disturbed.
  - 1. Do not reuse shoulder material if contaminated by foreign material.
    - a. Replace with new material of same quality and gradation.
  - 2. Materials and Methods of Construction: follow jurisdictional requirements and with applicable permits secured for this Project.
  - 3. Surface areas adjacent to shoulders, if left unstable by construction, with stabilized gravel or other acceptable stabilizing material.
- H. Restore pavement, curbs, other paved areas, and sidewalks following requirements elsewhere in Contract Documents.

#### 1.4 DISPOSAL OF WASTE AND EXCESS MATERIALS

- A. Dispose of construction waste and excess materials in authorized County disposal area or in area covered by current grading or sediment control permit.
  - 1. See Section 01110.
- B. Remove waste and excess material disposed of in unauthorized area, and restore area to its condition before disturbance.
- C. Dispose of human waste in special sites designated therefor.

## 1.5 REMOVAL OF REJECTED MATERIAL

- A. Remove material delivered to Project site, which has been determined by Contract Manager to be unsuitable or not following Contract Documents, and dispose of in approved area.

PART 2 PRODUCTS  
NOT USED

PART 3 EXECUTION  
NOT USED

**\*\*WSSC\*\***